

BRUHAT BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARI NAGAR ZONE
WORK ORDER SCHEDULE 'B'

Name of Work : Providing and repairing damaged LT Cable at JP Park Play ground in ward No 17

Name of the Agency: Prema Electrical Enterprises

Sl.No	Qty	Description of Item	Unit	Rates as per Sanctioned estimate		Amount
				In figure	In words	
1		Supplying PVC/GI flexible conduit pipe...mm dia fixing on surface over inverted tapered wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and on either end of the pipe terminated completely				
	50	20mm	Mtr	23.00	Rupees Twenty Three Only	1150.00
2		Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.				
	150	4 core 16 sqmm	Mtr	140.40	Rupees One Hundred and Forty Only Paise Forty Only	21060.00
	50	3.5 core 25 sqmm	Mtr	165.60	Rupees One Hundred and Sixty Five Only Paise Fifty Nine Only	8280.00
	50	3.5 core 35 sqmm	Mtr	204.00	Rupees Two Hundred and Four Only	10200.00
	30	3.5 core 50 sqmm	Mtr	265.00	Rupees Two Hundred and Sixty Five Only	7950.00
3		Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct.				
	150	6 sqmm to 16 sqmm	Mtr	10.80	Rupees Ten Only Paise Eighty Only	1620.00
	130	25 sqmm to 75 sqmm	Mtr	16.20	Rupees Sixteen Only Paise Nineteen Only	2106.00
4		Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. (As per Civil SR KSRB I-2, P-7)				
	230	In soil (ordinary)	Mtr	78.00	Rupees Seventy Eight Only	17940.00
5	230	Providing and filling sand in excavated trench to cover already laid UG cable to a depth of 150mm all-round the cable.	Mtr	103.00	Rupees One Hundred and Three Only	23690.00
6		Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc. GI Wire				
	25	8 SWG	Mtr	19.50	Rupees Nineteen Only Paise Fifty Only	487.50
7	10	Supplying and fixing of Spiral Earth Electrodes as per standard technical specification as per BESCOM.	Each	544.00	Rupees Five Hundred and Forty Four Only	5440.00
Total						99924.00

Tender Premium: -0.35% below

I Agree to carry Out this work at **-0.35%** Below the rates notified above as per the directions of Engineer incharge of Work


Contractor


Executive Engineer(Electrical)
Rajarajeshwarinagar zone, BBMP